



2.3 Site Perimeter Controls

The contractor must set site perimeter controls to protect areas downstream from erosion, sediment and flooding problems.

Area of Concern	Site Perimeter Control
Disturbed areas or slopes that drain toward adjacent properties	Continuous berms, silt fences, sandbags
Stabilizing area after grading has been completed	Mulching, seeding, planting, emulsifiers, or a combination of two or more
Off site flows that enter the constructions site	Continuous berms, earth dikes, drainage swales and lined ditches
Concentrated flows that leave the construction site	Outlet control measures that will dissipate velocities

Additional controls within the interior of construction site should supplement perimeter controls once rough grading is complete.