



**NOTES**

- ALL CONCRETE SHALL BE K.D.O.T. CLASS "A"
- A TWO (2) INCH LIFT (COMPACTED) OF DENSE GRADED AGGREGATE SHALL BE INSTALLED PRIOR TO PLACEMENT OF CONCRETE.
- CONTRACTION JOINTS SHALL BE PLACED AT FIVE (5) FOOT INTERVALS.
- EXPANSION JOINTS SHALL BE PLACED AT FIFTY (50) FOOT INTERVALS AND ALONG ALL EDGES BUTTED NEXT TO FIXED OBJECTS.
- MAXIMUM SLOPE ACROSS SIDEWALK SHALL BE 1/4" PER FOOT TOWARD ROAD UNLESS OTHERWISE NOTED.

**TURNDOWN SIDEWALK DETAIL  
(TYPICAL SECTION)  
(N.T.S)**



**CITY OF BOWLING GREEN  
PUBLIC WORKS  
PLANNING AND DESIGN**

**Turndown Sidewalk Detail**

J:\DWG\Detail\Turndown Sidewalk.dwg

**SHEET 1 OF 1**

JOB NO. \_\_\_\_\_ SCALE \_\_\_\_\_ DATE \_\_\_\_\_  
N/A N/A 17 Aug 2023