



**NOTES:**

1. Class A Concrete with Polypropylene Fiber.
2. Curtain Wall shall be constructed at Beginning and End of Ditch.
3. If a Construction Joint is used in the placing of the Ditch, it shall be constructed as Detailed.
4. Intermediate Anchors shall be used on Grades 20% or Steeper and spaced every 20 feet.
5. Tooled Joints shall be placed every 20 feet (Max.)
6. Broom finish perpendicular to flow.
7. All Reinforcing Steel shall be Grade 60.



**City of Bowling Green**

Public Works Planning and Design  
1011 College Street  
Bowling Green, Kentucky 42101

**SLOPED BOTTOM  
PAVED DITCH**

STANDARD DRAWING NO. **SMP-08-03**

APPROVED BY: \_\_\_\_\_ DIRECTOR OF ENGINEERING \_\_\_\_\_ DATE \_\_\_\_\_

SUORCE: LOUISVILLE MSD